


*J. E. Jameson*

REPUBLIC NATURAL GAS CO.  
Romine No. 5

SEC. 18 T. 11 R. 16W  
SE NW NW

Total Depth. 3303  
Comm. 9-29-37 Comp. 11-5-37  
Shot or Treated. 1000 gal acid.  
Contractor. Sam Murphy.  
Issued. 12-11-37

County Ellis.



CASING.

15 1/2" 94'  
10" 976'  
7" 3299'2"

DEC 11 1937

Elevation.

Production. Pot. 2690.76 B.

Figures Indicate Bottom of Formations.

clay and sand	70
shale and shells	328
sand and shale	390
sand	460
shale and sand	575
sand	635
shale and sand	730
red rock and sand	962
sand	966
anhydrite	1005
red bed	1150
shal & red bed	1318
shale and salt	1535
shale and shells	1575
shale and lime	1665
lime	1690
shale and lime	1867
lime	1900
lime and shale	1925
lime	1977
shale	1995
lime	2025
lime and shale	2140
lime	2155
shale	2163
shale and shells	2248
lime	2289
shale and lime	2410
shale blk	2416
shale and shells	2530
broken lime	2549
lime	2588
lime and shale	2623
shale and shells	2690
lime and shale	2740
lime	3195
lime and shale	3250
conglomerate	3280
shale blue	3293
shale blue & sand	3298
Top siliceous lime	3298
Siliceous lime	3303
Total Depth.	