

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY  
508 E. Murdock Wichita, Kansas


Company - J. M. HUBER & FERGUSON  
Farm - Potter "A" No. 4

SEC. 19 T. 11 R. 16W  
CN<sub>2</sub> NW SE

Total Depth. 3463  
Comm. 5-28-49 Comp. 7-20-49  
Shot or Treated.  
Contractor. J. M. Huber  
Issued. 8-27-49

County. Ellis

KANSAS



Elevation. 1862 *and*  
Phys. Pot.

Production. 77 bbls oil  
+ 9% wtr

Figures Indicate Bottom of Formations.

shale sdy	100
red bed & shale	400
shale, shells, redbed	1040
lime, shale, red bed	1345
salt, shale & shells	1575
lime & shale	2030
lime	2100
lime & shale	2195
shale, shells sdy	2365
shale & lime	2950
lime, cherty	2985
lime brkn	3001
lime & shale	3030
lime	3151
lime & shale	3180
lime	3251
lime & shale	3286
lime & shale	3463
Total Depth	

Logs: Sample	
Heebner	3023
Toronto	3045
Lansing	3072
cherty Congl	3338
shaley Congl.	3346
Simpson Shale-	3370
Simpson sand	3373
Arbuckle	3382

D.S.T. 2983-3001, open 25 mins. died in 20 mins., rec. 6' of mud, no bottom hole press.

D.S.T. 3045-65, open 25 mins. rec. 60' of mud.

D.S.T. 3113-51, open 35 mins. died in 30 mins., rec. 30' of mud, no bottom hole press.

D.S.T. 3383-90 open 50 mins., rec. 10' of wtr, 10' of mud, 15' of heavy oil cut mud. Bottom hole press, 700%.

90, Acidized w/500  
os per hr, 4.7 bbl  
show wtr.



This says:  
Perf. 12 holes 3486-90,  
stats. Bailed 10 times per hr,  
1 oil per hr. small show wtr.