


WELL LOG BUREAU — KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - J. M. HUBER, ET AL
Farm - Potter-Slimmer No. 2

SEC. 19 T. 11 R. 16W
NE SW SE

Total Depth. 3354'
Comm. 4-21-48. Comp. 7-23-48 ✓
Shot or Treated.
Contractor. Crowe Drilling Co., Inc.
Issued. 8-28-48

County. Ellis
KANSAS



Elevation. 1839 *ft.*

CASING:

8 5/8" 1000' cem w/500 Sx.
5 1/2" 3349' cem w/150 Sx.

Production. Pot. 1310 Bbls Oil
plus 44% water.

Figures Indicate Bottom of Formations.

shells & shale	315
shale & shells	460
sand	520
shale & shells	710
shells & shale	725
lime & shale	1000
shells & shale	1013
anhydrite	1060
shale	1260
shale & lime	1945
lime	1965
shale & shells	2010
shale	2035
lime	2060
lime & shale	2080
lime	2125
shale & shells	2205
shale & lime	2540
lime & shale	2615
shale & shells	2670
shale	2769
lime	2855
lime & shale	2890
lime	3040
shale & K.C. lime	3100
shale & lime	3110
lime	3333
Simpson shale	3347
Arbuckle lime	3349
lime	3354
total depth	

Tops:
Heebner 3001
Toronto 3023
Lansing 3047
B/Kansas City 3289
Simpson 3324
Arbuckle 3347-54

HDST 3349-54, open $\frac{1}{2}$ hr,
recovered 400' oil, no
water. Drilled cement
and cleaned out to 3354'.

Swabbed as follows:
38 Bbls oil plus 20 $\frac{1}{2}$ Bbls.
water 1st hr.
16 Bbls oil plus 27 $\frac{1}{2}$ Bbls.
water 2nd hr.
346 Bbls. oil plus 54 Bbls.
water/16 hrs.
500' off bottom.