

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.


668

SINCLAIR PRAIRIE OIL CO.
N.R. Slimmer No. 2

SEC. 19 T. 11 R. 16W
SE NW SW
330' fsth & E lines NW $\frac{1}{4}$ SW $\frac{1}{4}$

Total Depth 3398
Comm. 9-1-41 Comp. 9-20-41
Shot or Treated.
Contractor Harbar Drilling Co.
Issued. 11-1-41

County Ellis



CASING.

85/8" 1039' Meas. fr bottom of cellar.
85/8" 1068' Meas. fr Top of Rotary.

5 $\frac{1}{4}$ 3395'

Elevation.

Production. Pot. 78 B.
no water.

Figures Indicate Bottom of Formations.

shale and sholls	110
shale and sand	225
sand and shalo	245
shale and sholls	400
shale and sholls	440
sand	650
limo	670
sand & limo sholls	800
red bod and shale	960
shale and sholls	1055
anhydrite	1105
shale - red bod	1140
red bod and shalo	1290
edy shalo	1300
shalo	1330
shale and sholls	1365
shale and sholls	1480
salt and sholls	1620
shale	1635
shale and sholls	1690
limo	1735
lime and shalo	1765
limo	1795
shalo	1845
lime and shale	1885
shale and lime	1975
limo	2015
shale and limo sholls	2025
limo	2125
lime broken	2325
lime and shale	2410
shale limo sholls	2435
shalo	2475
limo shells	2490
shalo	2570
shale and lime	2670
shale limo sholls	2755
broken limo shale	2800
lime Topoka	2815
lime	3350
limo sdy	3355
limo	3372
lime and groon shale	3382
shalo	3395
sand	3395
chert	3397
limo	3398
Total Depth.	

Top of Arbucklo 3395 Rig Floor.

Used 250 gal acid to clean up hole after
drilled in.