

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- FRANCO CENTRAL OIL CO.
Farm- Potter No. 14

SEC. 20 T. 11 R. 16W
SW SE SW

Total Depth. 3390'

Comm. 1-26-59

Comp. 2-6-59


Shot or Treated.

Contractor. Red Tiger Drilg. Co.

Issued. 3-28-59

County Ellis

KANSAS



Elevation. 1780' RB

Production. 100 BOPD

CASING:

8 5/8" 982' cem w/450 sx.
5 1/2" 3390' cem w/100 sx.

Figures Indicate Bottom of Formations.

sod	25
post rock, shale	40
shells & shale	225
red bed & shale	315
shale & shells	405
sand & shale	600
shale & shells	700
shale, shells & red bed	962
Anhydrite	1000
redbed, shale & shells	1445
shale & shells	1575
lime & shale	2090
shale & lime shells	2175
shale & lime	2835
lime	2878
lime & shale	2965
lime	3302
lime & shale	3307
lime	3320
Arbuckle	3390
Total Depth	

TOPS: SCOUT

Anhydrite	962
Topeka	2705
Heebner	2943
Toronto	2969
Lansing	2992
Base Kansas City	3220
Simpson Sand	3302
Arbuckle	3308