


WELL LOG BUREAU — KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company. HUBER & GROVE
Farm. Don Chrysler No. 1

SEC. 22 T. 11 R. 16
NW NW SW

Total Depth. 3460
Comm. 4-1-49 Comp. 7-12-49
Shot or Treated.
Contractor. Brunson Drlg. Co.
Issued. 8-13-49

County. Ellis KANSAS



Elevation. _____

CASING:
8 5/8" 1001
5 1/2" 3305

Figures Indicate Bottom of Formations.

sand	20
shale, rock & pyrite	150
shale & shells	400
sand & shale	740
shale & shells	830
red bed	995
anhyd.	1065
redbed & shale	1480
salt & shale	1695
shale & shells	1840
shale	1975
shale & lime	2050
lime	2225
lime & shale	2320
lime brkn	2615
shale & lime	2725
lime brkn	2790
lime & shale	2845
lime brkn	2918
lime cherty & sharp	2963
lime brkn	3010
lime & shale	3045
lime	3092
lime & shale	3111
lime	3130
lime cherty	3173
lime	3376
congl. cherty	3390
shale	3395
shale & congl.	3425
lime Arbuckle	3460
Total Depth	

Production. 54 bbls. oil
+ 72 bbls wtr/24 hrs.
Ran Shhlumberger, Ran Lane-ells Comb-
ination log.
Perf. 36 holes 3100-3112, bailed + bbls
oil per hr. Acidized w/2000 gals,
Pressured up to 100%. Broke to 70%.
Swabbed down & swabbed 12 to 14 bbls.
oil per hr. for 3 hrs. Cleaned out on
bottom. Pumped 55 bbls. oil plus 70%
wtr/24 hrs.
Physical Potential-54 bbls oil plus 72
bbls wtr/24 hrs.

Sample Tops:

Anhyd.	998
Topeka	2782
Heebner	3012
Toronto	3028
Lawrence	3060
Base K.C.	3305
Lawrence Cherty lime	3357
Cherty Congl.	3357
Simpson	3410
Arbuckle	3425

D.S.T. 3093-3111, open 30 ms. rec.
150' oil cut mud, bottom hole press.
970' in 10 ms.

3-4 streaks of porosity, few spotted
showing, faint odor 3138-60

D.S.T. 3136-73, open 30 ms. rec. 480'
salt wtr.

V. S. S. O.	3028-33
V. S. S. O.	3069-71
F. S. O.	3093-96
F. S. O.	3161-10