


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- PABCO DRILLING CO.
 Farm- Glick No. 1

SEC. 22 T. 11 R. 6W
 SW SW NW

Total Depth. 3137
 Comm. 4-1-52 Comp. 4-13-52
 Shot or Treated.
 Contractor. Pabco Drilling Co.
 Issued. 7-12-52

County Ellis
 KANSAS



CASING:

8 5/8" 1015 cem. w/525 sx.
 5 1/2" 3137 cem. w/135 sx.

Elevation. 1850

Production. Pmp. 20 bbls. & no
 wtr.

Figures Indicate Bottom of Formations.

shale & sholls	275
shale & sand	300
shale	370
sand	405
shale & s hells	610
sand	715
shale & shells	830
shale & red beds	1005
anhyd.	1015
shale, shells & redbeds	1290
shale & red beds	1400
salt & shale	1600
shale & shells	1655
lime & shale	1820
lime	1900
lime & shale	2150
shale & sdy lime	2615
shale & lime	2720
lime	2933
lime & shale	3046
shale	3048
lime	3078
lime & shale	3091
lime	3108
lime	3137
Total Depth	

Tops: Scout	
Topeka	2782
Heebner	3018
Toronto	3037
Lansing	3065

D.S.T. 3018-14

drilled out cem. to 3113 ran SML Rad. log.
 & perf. casing w/36 jet shots from 3093-
 3102. Small show free oil, az. w/3000
 gal. thru casing, tested 11-12 gal oil per
 hr. for 12 hrs. Re-acidized w/1000 gal.
 testing 26 gal. per hr for 12 hrs. Set
 plug @ 3050. Perf. 24 jet shots 3038-42.
 Az. w/1000 gals. Swab thru casing 8 bbl. oil
 in 14 hrs. Drld. out plug set @ 3050
 testing both perforated zones together.