

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,


Wichita, Kansas

Company- **FRANCO CENTRAL OIL CO.**
 Farm- **Potter** No. **6**

SEC. **29** T. **11** R. **16W**
 NE NE NW

Total Depth. **3348'**
 Comm. **8-21-57** Comp. **8-31-57**
 Shot or Treated.
 Contractor. **Lewis Drlg. Co.**
 Issued. **11-23-57**

County **Ellis**
 KANSAS



CASING:
 8 5/8" 947'
 5 1/2" 3344'

Elevation. 1765' KB

Production. **152 BOPD**

Figures indicate Bottom of Formations.

sand & shale	475
blue shale	500
sand	560
red bed & shale	914
Anhydrite	970
shale & lime	2085
lime	2375
shale & lime	2840
lime	3284
Arbuckle lime	3348
Total Depth	

TOPS:	
Anhydrite (Scout)	920
Topeka	2682
Heebner	2921
Toronto	2944
Lansing	2972
Base Kansas City	3233
Simpson	3260
Simpson Sand	3270
Arbuckle	3276