


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- **HEATHMAN-SEELIGSON DRILLING CO.**
 Farm- **Potter "F" No. 1**

SEC. 29 T. 11 R. 167
 SW NW SE

Total Depth. **3398'**
 Comm. **4-13-55** Comp. **4-24-55**
 Shot or Treated.
 Contractor. **Heathman-Seeligson Drlg. Co.**
 Issued. **5-21-55**

County **Ellis**
KANSAS



CASING:
 10 3/4" 160' cem w/135 sx

Elevation. 1832' DF

Production. **Dry**

Figures indicate Bottom of Formations

shale & shells	160
blue shale & shells	300
red bed & shells	450
sand	480
red bed & shells	560
sand	715
red bed & shale	860
shale & shells	1005
anhydrite	1050
shale; lime & shells	1065
shale, shells & red bed	1740
lime & shale	1800
shale & shells	1917
lime & shale	2695
broken lime	2785
lime	3260
lime & shale	3385
lime	3398
Total Depth	

Tops: (KB)	
Heebner	3000
Leasing-Kansas City	3047
Conglomerate	3344
Arbuckle	3388

DRILL STEM TESTS:

- #1 2946-2980, open 1 hr., good blow for 30 min., rec. 690' formation water, rainbow show of oil. BHP 1185# in 20 mins.
- #2 3126-3142, open 1 hr., good blow for 30 min.; then decline to weak intermittent blow, tool rec. 960' formation water w/ rainbow show oil. BHP 1185# in 20 min. IFP 270#; FFP 450#.