

Plotted - *AW*


[Plotted Texas CO.

CITIES SERVICE OIL CO.
DeHoff No. 2.

SEC. 30 T. 11 R. 16 W
NW SW NW
1065' N 330' E W 1/4 Cor.

Total Depth. 3376'
Comm. 6-4-42 Comp. 6-25-42
Shot or Treated. 2000 Gals. 6-28-42
Contractor. Mabee O.G. Co.
Issued. 8-15-42

County. Ellis



CAS ING:
8 5/8" 1051' Cem.
5 1/2" 3361' Cem.

Elevation.

Production. Echo. Pot. 1768 B.
No wtr

Figures Indicate Bottom of Formations.

shale & shells	0-465
sand & shale	585
shale & shells	660
sand	715
shale & shells	735
sand & shale	780
shale, shells, red bed	1030
shale	1065
anhydrite & lime	1070
anhydrite	1102
red bed & shale	1225
shale & shells	1735
lime & shale	2078
lime	2123
lime brkn	2190
shale & lime	2567
shale & shells	2834
lime	3365
3365 Rot. TD = 3363 SIM	
dolomite	3376
Total Depth.	

Corr. Top Arbuckle 3361
Penetration 15

Fillup:

150' oil in 30 min at 3367
300' oil in 2 hrs at 3371
700' oil in 4 1/2 hrs at 3376
1000' oil in 6 hrs at 3376
1200' oil in 7 hrs at 3376
1800' oil in 9 hrs at 3376