


WELL LOG BUREAU — KANSAS GEOLOGICAL SOCIETY
 412 Union National Bk. Bldg., Wichita, Kansas

Company - **CITIES SERVICE OIL CO.**
 Name - **DeHoff** No. **5**

SEC. **30** T. **11** R. **16 W**
 NW SE NW
 990' N & 990' W of Center

Total Depth. **3378'**
 Comm. **9-20-45** Comp. **10-25-45**
 Shot or Treated, **1000 gals. acid 10-19-45; 1000 gals. 10-25-45**
 Contractor. **Corbett-Barbour Drilg. Co.**
 Comm. **12-8-45**

County. **Ellis**
KANSAS



Elevation. **1826** *rk*

Production. Phy: Pot. **58 BO, 116 BW**

CASING:

8 5/8" **1805'** Cement
5 1/2" **3541'** Cement

Figures Indicate Bottom of Formations.

surface clay & sand	0-39
sand	70
shale & shells	125
shale & iron	260
shale	360
shale & shells	450
sand & shells	535
shale	610
sand & shells	650
shale	720
shale & shells	780
red bed & shells	795
shale	1004
anhydrite	1055
red bed & shells	1150
shale & shells	1255
shale	1390
salt	1650
salt shells & shale	1755
shale & shells	1875
lime	2000
shale & lime	2160
lime	2220
lime & shale	2580
shale	2695
shale & lime	2810
lime	2856
shale & lime	2885
lime	2955
lime & shale	3100
lime	3325
shale	3340
lime	3344
3344 Rot. T.D. 3344 SLM	
dolomite	3378
Total Depth:	

Top Ar buckle **3340'**
 Penetration **38'**

Show oil **3348-62'**
1000 acid @ T.D. 3362'
 Pumped **36 B** fluid (64% wtr.)
 in 24 hrs.
 Deepened **3362-78'**