

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas


Company - CITIES SERVICE OIL CO.
Farm - DeHoff No. 6

SEC. 30 T. 11 R. 16W
NE NE NW
330' S & 330' W of N $\frac{1}{4}$ Corner

Total Depth. 3329' ✓
Comm. 4-9-48 Comp. 5-15-48
Shot or Treated. Acid. W/4000 gallons (see below)
Contractor. Corbett & Barbour Drlg. Co.
Issued. 7-10-48

County. Ellis

KANSAS



Elevation. 1809 feet

Production. Phy. Pot. 67 BO,
no wtr, 24 hrs.

Figures Indicate Bottom of Formations.

clay & rock	80
sand	210
shale	550
sand	690
red bed & shells	1025
shale & red bed	1335
salt	1590
shale " shells	1830
shale	2030
lime	2080
shale & lime	2230
lime	2325
lime & shale	2520
lime	2560
shale	2575
lime & shale	2805
lime	3290
sand & lime	3293
3293' RTD = 3289 SLM	
lime	3329
Total Depth	

Tops Corr.:
Lansing 3004
Arbuckle 3287
Penetration 42

Fill-up:

150' oil in 8 hrs 20 min at 3309'
200' oil in 10 hr 20 min at 3309'
490' oil in 23 hr 20 min at 3314'

5-4-48 acidized 1000 gals. at 3314'
5-10-48 deepened 3314-24
5-11-48 acidized 1500 gallons.
5-13-48 pumped 56 oil, 2 acid wtr, 24 hr.
5-15-48 deepened 3324-29
5-17- acidized 1500 gallons
5-19-48 pumped 78 oil, 2% acid wtr, 24 hr.