

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas


Company- TENNESSEE GAS TRANSMISSION CO.
Farm- Lydia DeHoff No. 1

SEC. 30 T. 11 R. 16W
SE SE SW

Total Depth. 3480'
Comm. 12-2-57 Comp. 12-13-57
Shot or Treated.
Contractor. Peel Brothers, Inc.
Issued. 7-12-58

County Ellis

KANSAS



Elevation. 1871' RB

CASING:
8 5/8" 203' cem.

Production. Dry

Figures Indicate Bottom of Formations.

shale	20
post rock	45
shale & sand	340
red rock	590
sand	700
red rock	810
shale & shells	1050
anhydrite	1085
shale	1795
shale & lime	1970
lime	2205
lime & shale	2500
shale	2655
shale & lime	2885
lime	2948
lime & shale	3100
lime	3250
lime & chert	3325
lime	3390
Conglomerate	3404
lime	3480
Total Depth	

TOPS:

Heebner	3044
Toronto	3069
Lansing-Kansas City	3093
Base Kansas City	3312
Conglomerate Shale	3350
Conglomerate Cherty	3362
Weathered Arbuckle	3404
Solid Arbuckle	3418

DST #1 3125-95, op 1 hr, rec. 38' VSOCM,
BHP 737-148

DST #2 3350-90, op 30 mins, rec. 30' drlg.
mud with few specks oil, BHP 108, FP 36.

DST #3 3405-3409, op 1 hr, rec. 20' mud,
BHP 198, FP 30.

DST #4 3408½-13, op 30 mins, rec. 12'
mud, BHP 1295, FP 48.