

No. 20
Card

WELL LOG

COMPANY **Franco Central Oil Company**

SEC. ²⁰~~30~~ T. 11S R. 16W
LOC. SW¹/₄ NW¹/₄ SE¹/₄

FARM **Potter**

NO. **1**

TOTAL DEPTH **3316'**
COMM. **8-4-56**


COMP. **8-13-56**

COUNTY **Ellis**
KANSAS

SHOT OR TREATED

CONTRACTOR **Lewis Drilling Company**

ISSUED



CASING

20	10		
15	8 5/8"	955'	
12	6		
13	5 1/2"	3316'	

ELEVATION **1768 K.B.**

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

0 - 100	Clay
100 - 125	Clay & Sand
125 - 395	Shale & Chalk
395 - 500	Hard Sand, Shale
500 - 610	D Sand
610 - 755	Pyrite & Shale ✓
755 - 940	Red Bed
940 - 970	Anhydrite
970 - 1285	Shale & Red Bed
1285 - 1640	Shale & Shells
1640 - 1920	Shale Lime
1920 - 1979	Ft. Riley
1979 - 2160	Lime
2160 - 2840	Shale Lime
2840 - 2855	Lime
2855 - 2955	Lime Shale
2955 - 3025	Lime
3025 - 3063	Lime & Shale
3063 - 3162'	Lime
3162 - 3215	Shale & Lime
3215 - 3316	Lime
3316 - T. D.	

Geologic Tops:

Anhydrite	945'
Topeka	2699'
Heebner	2934'
Toronto	2958'
Lansing	2981'
Arbuckle	3308'