

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


Company- HEATHMAN & COMPANY
Farm- Chrisler No. 1

SEC. 33 T. 11 R. 16W
NW NW NW

Total Depth. 3433
Comm. 7-21-53 Comp. 8-2-53
Shot or Treated.
Contractor. Strain Drilling Co.
Issued. 9-5-53

County Ellis

KANSAS



Elevation. 1828 RB

Production. Dry

CASING:
8 5/8 @ 760' w/ 400 sx cem.

Figures Indicate Bottom of Formations.

soil & shale	20
post rock	65
shale & shells	270
sand & shale	290
shale, shells & sand	390
sand & shale	495
shale	530
Dakota sand	650
shale, shells & red bed	754
red bed	775
shale, shells & red bed	992
anhydrite	1030
shale & shells	1600
lime & shale	1690
lime	1710
lime & shale	2005
lime	2060
lime & shale	2780
lime	3360
conglomerate	3370
cherty conglomerate	3433
Total Depth	

TOPS:	
Anhydrite	992
Topeka	2756
Heebner	3000
Toronto	3022
Lansing	3047
Base KC	3270
Conglomerate	3337
Arbuckle	3423

DST #1: 3330-65, open 1 hr. rec. 40'
watery mud, wk bio thruout (1 hr. 20 min.)
BHP 880#

Ran Schlumberger

RB Measurements