

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

500 East Murdock,


Wichita, Kansas

Company- DAVIS BROS. & TRANSIT CORP.
Farm- Chrisler "H" No. 1

SEC. 36 T. 11 R. 16W
C NW SE

Total Depth. 3482'
Comm. 5-12-59 Comp. 5-24-59
Shot or Treated.
Contractor. Transit Corp.
Issued. 10-31-59

County Ellis
KANSAS



Elevation. 1716' KB

CASING:

8 5/8" 878' cem w/475 sx.
4" 3460'

Production. 15 BOPD

Figures Indicate Bottom of Formations.

surface clay	40
sand	60
shale	115
sand	130
shale	255
sand	265
shale & pyrite strks	330 ✓
sand	342
sandy shale	360
sand	365
shale & pyrite	395 ✓
sand & pyrite	403 ✓
shale	425
sand	515
red bed	750
shale & red bed	873
Anhydrite	905
shale	1550
lime w/shale streaks	1830
lime	1970
shale	2040
lime & shale	2175
shale & lime	2510
lime & shale	2797
lime	3330
Cherty conglomerate	3384
lime & conglomerate	3425
chert & lime	3462
lime	3482
Total Depth	

TOPS:

Anhydrite	875
Topeka	2659
Heebner	2913
Toronto	2932
Lansing	2962
Base Kansas City	3210
Conglomerate	3266
Simpson Shale	3394
Arbuckle	3437