

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

RECEIVED

JUN 20 2005

Form ACO-1
September 1999
Form Must Be Typed

WELL COMPLETION FORM
WELL HISTORY - DESCRIPTION OF WELL & LEASE

AMENDED

KCC WICHITA

COPY

Operator: License # 32754
Name: Elysium Energy, L.L.C.
Address: 1625 Broadway, Suite 2000
City/State/Zip: Denver, CO 80202
Purchaser: NCRA
Operator Contact Person: Chris Gottschalk
Phone: (785) 434-4638
Contractor: Name: Discovery Drilling Co., Inc.
License: 31548
Wellsite Geologist: Ron Nelson

API No. 15 - 051-25396-0000
County: Ellis
W2 Sec. 27 Twp. 11 S. R. 17 East West
2550 feet from S / N (circle one) Line of Section
1360 feet from E / W (circle one) Line of Section

Footages Calculated from Nearest Outside Section Corner:
(circle one) NE SE NW SW
Lease Name: Baumer "B" Well #: 54
Field Name: Bemis-Shutts
Producing Formation: Arbuckle
Elevation: Ground: 2023' Kelly Bushing: 2031'
Total Depth: 3565' Plug Back Total Depth: 3545'
Amount of Surface Pipe Set and Cemented at 212.9 Feet
Multiple Stage Cementing Collar Used? Yes No
If yes, show depth set _____ Feet
If Alternate II completion, cement circulated from 3562
feet depth to surface w/ 500 sx cmt.

Drilling Fluid Management Plan
(Data must be collected from the Reserve Pit)
Chloride content 14000 ppm Fluid volume 320 bbls
Dewatering method used Evaporation
Location of fluid disposal if hauled offsite:
Operator Name: _____
Lease Name: _____ License No.: _____
Quarter _____ Sec. _____ Twp. _____ S. R. _____ East West
County: _____ Docket No.: _____

Designate Type of Completion:
 New Well Re-Entry Workover
 Oil SWD SIOW Temp. Abd.
 Gas ENHR SIGW
 Dry Other (Core, WSW, Expl., Cathodic, etc)

If Workover/Re-entry: Old Well Info as follows:
Operator: _____
Well Name: _____


Original Comp. Date: _____ Original Total Depth: _____
 Deepening Re-perf. Conv. to Enhr./SWD
 Plug Back _____ Plug Back Total Depth _____
 Commingled _____ Docket No. _____
 Dual Completion _____ Docket No. _____
 Other (SWD or Enhr.?) _____ Docket No. _____

2/22/05 2/26/05 3/15/05
Spud Date or Date Reached TD Completion Date or
Recompletion Date Recompletion Date

INSTRUCTIONS: An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information of side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature: _____
Title: Regulatory Engineer Date: 6/16/2005
Subscribed and sworn to before me this 16th day of June
19 2005
Notary Public: Mendi Larue
Date Commission Expires: 8/26/06



KCC Office Use ONLY
Letter of Confidentiality Attached
If Denied, Yes Date: _____
Wireline Log Received
Geologist Report Received
UIC Distribution

My Commission Expires 8/26/2006

COPY RECEIVED

JUN 17 10 59 2005

Operator Name: Elysium Energy, L.L.C. Lease Name: Baumer
 Sec. 27 Twp. 11 S. R. 17 East West County: Ellis

KCC WICHITA

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No <i>(Attach Additional Sheets)</i> Samples Sent to Geological Survey <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Cores Taken <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Electric Log Run <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <i>(Submit Copy)</i> List All E. Logs Run: Sonic, Induction, Micro, CNL/CDL	<table border="1" style="width:100%; border-collapse: collapse;"> <tr> <td><input checked="" type="checkbox"/> Log</td> <td>Formation (Top), Depth and Datum</td> <td><input type="checkbox"/> Sample</td> </tr> <tr> <td>Name</td> <td>Top</td> <td>Datum</td> </tr> <tr> <td>Top Anhydrite</td> <td>1242</td> <td>+789</td> </tr> <tr> <td>Topeka</td> <td>2949</td> <td>-918</td> </tr> <tr> <td>Toronto</td> <td>3204</td> <td>-1173</td> </tr> <tr> <td>LKC</td> <td>3229</td> <td>-1198</td> </tr> <tr> <td>Arbuckle</td> <td>3505</td> <td>-1474</td> </tr> </table>	<input checked="" type="checkbox"/> Log	Formation (Top), Depth and Datum	<input type="checkbox"/> Sample	Name	Top	Datum	Top Anhydrite	1242	+789	Topeka	2949	-918	Toronto	3204	-1173	LKC	3229	-1198	Arbuckle	3505	-1474
<input checked="" type="checkbox"/> Log	Formation (Top), Depth and Datum	<input type="checkbox"/> Sample																				
Name	Top	Datum																				
Top Anhydrite	1242	+789																				
Topeka	2949	-918																				
Toronto	3204	-1173																				
LKC	3229	-1198																				
Arbuckle	3505	-1474																				

CASING RECORD <input checked="" type="checkbox"/> New <input type="checkbox"/> Used							
Report all strings set-conductor, surface, intermediate, production, etc.							
Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs. / Ft.	Setting Depth	Type of Cement	# Sacks Used	Type and Percent Additives
Surface	12-1/4"	8-5/8"	23	212.9	Common	160	2% gel, 3%CC
Production	7-7/8"	5-1/2"	15.5	3562	SMDC	360	11.2 ppg
						150	14 ppg

ADDITIONAL CEMENTING / SQUEEZE RECORD Cement did circulate				
Purpose:	Depth Top Bottom	Type of Cement	#Sacks Used	Type and Percent Additives
<input type="checkbox"/> Perforate <input type="checkbox"/> Protect Casing <input type="checkbox"/> Plug Back TD <input type="checkbox"/> Plug Off Zone				

Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used)	Depth
4	3519-22'		

TUBING RECORD		Size <u>2-7/8"</u>	Set At <u>3513'</u>	Packer At	Liner Run <input type="checkbox"/> Yes <input type="checkbox"/> No
Date of First, Resumed Production, SWD or Enhr. <u>3/15/2005</u>		Producing Method <input type="checkbox"/> Flowing <input checked="" type="checkbox"/> Pumping <input type="checkbox"/> Gas Lift <input type="checkbox"/> Other (Explain)			
Estimated Production Per 24 Hours	Oil Bbls. <u>2</u>	Gas Mcf	Water Bbls. <u>193</u>	Gas-Oil Ratio	Gravity

Disposition of Gas Vented Sold Used on Lease (If vented, Sumit ACO-18.)

METHOD OF COMPLETION Open Hole Perf. Dually Comp. Commingled 3519-3522'

Production Interval Other (Specify) _____