


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

Company- WHITE EAGLE OIL COMPANY
Farm- Katie Taylor No. 1

SEC. 1 T. 11 R. 17W
NE NW NE

Total Depth. 3527'
Comm. 7-7-57 Comp. 7-18-57
Shot or Treated.
Contractor. Peel Brothers, Inc.
Issued. 10-19-57

County Ellis KANSAS



Elevation. 1911' R.R.

Production. Dry

CASING:

8 5/8" @ 251'

Figures indicate Bottom of Formations.

clay	60
blue shale	130
shale & shells	252
sand & shale	550
sand & pyrite	600
sand	775
red rock & shale	780
shale & red bed	1115
anhydrite	1145
shale & red bed	1660
shale & shells	1935
shale & lime	2670
lime	3394
cherty cong.	3522
lime	3527
Total Depth	

TOPS: Electric Log

Topeka	2848
Heebner	3077
Toronto	3099
Lansing	3120
Conglomerate	3396
Arbuckle	3521

D.S.T. #1. 3121-3208 Open 1½ hrs. Weak, steady blow throughout test. No gas to surface. Rec. 150' drilling mud with specks of oil. No odor. IBHFP 80#. FBHFP 160#; SIBHP 900# (30 min.) HH 2060#.

D.S.T. #2. 3213-3270. Tool open 30 min. Weak blow for 11 min. Died. Rec. 15' drilling mud. No shows oil. BHFP 0#; SIBHP 740# (20 min.) HH 1920#.

D.S.T. #3. 3312-3394. Tool open 30 min. Weak blow for 6 min. Died Rec. 15' mud. No shows. BHFP 0#; SIBHP 725# (20 min.)

D.S.T. #4. 3520-3527. Tool open 1 hr. Weak blow initially, increased to good blow in 6 min. IBHFP 0#; FBHFP 350#; SIBHP 1120# (20 min.); HH 1980#.