

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.


Plotted EGC.

THE DICKEY OIL CO.
Henderson No. 2-B.

SEC 6 T. 11 R. 17W.
CW $\frac{1}{2}$ SW SW

Total Depth. 3493.
Comm. 4-21-40 Comp. 5-14-40
Shot or Treated.
Contractor.
Issued. 7-6-40

County Ellis.



CASING.

10" 1223'
7" 3487'

Elevation.

Production. Pot. 1482 B.

Figures Indicate Bottom of Formations.

shale and shells	710
sand	865
red bed	1205
anhydrite	1250
shale red bed	1355
shale and shells	1525
salt	1630
shale and shells	1772
shale	1785
broken lime	2194
lime	2280
shale and shells	2400
broken lime	2448
shale and shells	2762
shale and lime	2845
shale	2896
lime	3190
red bed	3200
shale and lime	3220
lime	3400
broken lime	3445
conglomerate	3460
dolomite	3476
shale green	3487
arbuckle lime	3488
lime	3493
Total Depth.	

Top Anhydrite	1205
Top Topeka lime	2896
Top K.C. lime	3220
Top Arbuckle	3487