

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bldg. Wichita, Kansas

Company - PETROLEUM, INC.
Farm - McCarroll No. 1

SEC. 6 T. 11 R. 17W
SE SW NE

Total Depth. 3535
Comm. 1-27-49 Comp. 2-15-49
Shot or Treated.
Contractor. Petroleum, Inc.
Issued. 3-12-49

County. Ellis
KANSAS



CASING:
8 5/8" 209' com w/125 sx., circulated

Elevation. 1957 ind.

Production. dry

Figures Indicate Bottom of Formations.

surface rock, shale	100
shale	130
shale, shell	400
redbed	470
shale	710
sand	890
redbed	1190
anhydrite	1250
shale, shell	1300
shale	1790
lime, shale	1880
shale	2030
shale, lime	2050
lime	2210
shale	2290
lime, shale	2495
shale	2620
lime, shale	3152
lime	3350
lime, shale	3415
lime	3485
chert, lime	3493
lime, shale	3516
shale	3535
total depth	

Tops:

Topoka	2921
Hoebner	3147
Dodge	3168
Lansing	3190
Arbuckle	3532

Plugging Record:

Mixed heavy mud and circulated.
Placed wooden plug at 206'.
Mixed and dumped 20 sx. cement
on top plug. Finished filling hole
w/heavy mud and placed 5 sx. cement
in top of surface casing.