

State Geological Survey
AFFIDAVIT OF COMPLETION FORM
WICHITA BRANCH

7-11-17W
 ACO-1

This form shall be filed in triplicate with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within ten days after the completion of the well, regardless of how the well was completed. Circle one: (Oil), gas, dry, SWD, OWWO, injection. Type and complete ALL sections. Applications must be filed for dual completion, commingling, salt water disposal and injection. X Attach wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.) KCC#-(316)263-3238.

OPERATOR LIBERTY ENTERPRISES, INC

API NO. 15-051-22,456

ADDRESS 308 West Mill

COUNTY Ellis

Plainville, Kansas 67663

FIELD Bemis-Shutts Field

**CONTACT PERSON Charles G. Comeau

PROD. FORMATION Arbuckle

PHONE 913-434-4686

LEASE Collins

PURCHASER Ashland Oil, Inc.

WELL NO. #3

ADDRESS P.O. Box 391

WELL LOCATION NW SW NW

Ashland, Kentucky 41101

1650 Ft. from North Line and

DRILLING PIONEER DRILLING COMPANY, INC.

330 Ft. from West Line of

CONTRACTOR

the NW/4 SEC. 7 TWP. 11S RGE. 17W


ADDRESS 308 West Mill

Plainville, Kansas 67663

PLUGGING

CONTRACTOR

ADDRESS



WELL PLAT

KCC _____
 KGS
 MISC _____
 (Office Use)

TOTAL DEPTH 3537' PBSD 3518'

SPUD DATE 6/25/81 DATE COMPLETED 7/31/81

ELEV: GR 1885' DF 1888' KB 1890'

DRILLED WITH ~~CASEY~~ (ROTARY) ~~TOOLS~~ TOOLS

(New) / ~~CASEY~~ casing.

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Socks	Type and percent additives
Surface	12 1/4"	8 5/8"	28#	1142'	60-40 poz Common	275 125	2% gel, 3% cc 2% gel, 3% cc
Production	7 7/8"	5 1/2"	14#	3530'	ASC 60-40 poz	75 100	6% gel

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Socks cement	Shots per ft.	Size & type	Depth interval
			4 per ft.		3451-52
			4 per ft.		3461-63
			approx. 1 per 1/2 ft.		3401-03
			2 per ft.		3393-97

TUBING RECORD

Size	Setting depth	Pecker set at
2 1/2"	3435'	

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
200 gallon acid	3451-52, 3461-63

Date of first production <u>7/31/81</u>	Producing method (flowing, pumping, gas lift, etc.) <u>Pumping unit</u>	Gravity <u>30°</u>
RATE OF PRODUCTION PER 24 HOURS	Oil <u>13</u> bbls.	Gas <u>95</u> %
Disposition of gas (vented, used on lease or sold)	Water <u>275</u> bbls.	Gas-oil ratio <u>275</u>
Perforations		

**The person who can be reached by phone regarding any questions concerning this information. A witnessed initial test by the Commission is required if the well produces more than 25 BOPD or is located in a Basic Order Pool.

Name of lowest fresh water producing stratum _____ Depth 100'

Estimated height of cement behind Surface Pipe cement circulated.

DV USED? None

WELL LOG

7-11-17W

Formation Description, Contents, etc.	Top	Bottom	Name	Depth
sand and shale	0'	442'		
sand and shale	442'	964'		
red bed and sands	964'	1134'		
anhydrite	1134'	1142'		
anhydrite	1142'	1166'		
shale and sand	1166'	1450'		
shale and lime	1450'	1787'		
shale and lime	1787'	1968'		
shale and lime	1968'	2117'		
shale and lime	2117'	2367'		
lime and shale	2367'	2610'		
shale and lime	2610'	2758'		
lime and shale	2758'	2899'	Topeka	2822'
lime and shale	2899'	3008'		
lime and shale	3008'	3110'	Heebner	3049'
lime and shale	3110'	3202'	Toronto	3075'
lime and shale	3202'	3211'	Lansing/KC	3095'
lime	3211'	3235'		
lime and shale	3235'	3317'		
lime and shale	3317'	3375'	Base/KC	3330'
lime and shale	3375'	3405'	Arbuckle	3396'
arbuckle	3405'	3490'		
lime and shale	3490'	3537'		
	3537'	RTD		

AFFIDAVIT

STATE OF KANSAS, COUNTY OF ROOKS SS, _____

Charles G. Comeau OF LAWFUL AGE, BEING FIRST DULY SWORN UPON HIS OATH

DEPOSES THAT HE IS Secretary-Treasurer (FOR)(OF) LIBERTY ENTERPRISES, INC.

OPERATOR OF THE Collins LEASE, AND IS DULY AUTHORIZED TO MAKE

THIS AFFIDAVIT FOR AND ON THE BEHALF OF SAID OPERATOR, THAT WELL NO. 3 ON

SAID LEASE HAS BEEN COMPLETED AS OF THE 31st DAY OF July, 1981, AND THAT

ALL INFORMATION ENTERED HEREIN WITH RESPECT TO SAID WELL IS TRUE AND CORRECT.

FURTHER AFFIANT SAITH NOT.

(S) [Signature]
Charles G. Comeau

SUBSCRIBED AND SWORN BEFORE ME THIS 20th DAY OF November 1981

SHARON GARVERT
NOTARY PUBLIC
STATE OF KANSAS
My Appt. Expires 10/24/84

MY COMMISSION EXPIRES:

[Signature]
NOTARY PUBLIC
Sharon Garvert