

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.  
412 Union National Bank Bldg, Wichita, Kansas.

*Plotted  
Am.*

DARBY PETROLEUM CORP.  
Henderson No. 4


SEC. 7 T 11 R. 17W.  
CN $\frac{1}{2}$  SE NW

Total Depth. 3455 $\frac{1}{2}$   
Comm. 10-5-39 Comp. 10-17-39  
Shot or Treated. 1500 gal acid.  
Contractor.  
Issued. 11-4-39

County. Ellis.

CASING.

15" 105' 10" 1142'  
7" 3445 CTD.



Elevation.

Production. Pot. 3500 B.  
Maximum

Figures Indicate Bottom of Formations.

sand	50
shale and shells	1137
anhydrite	1190
shale and red bed	1200
red bed shale and shells	1510
shale and shells	1605
salt	1705
shale and shells	1785
shale and lime	2595
shale	2675
shale and lime	2825
lime	3449
3449 equals 3446 SLM dolomite	3455 $\frac{1}{2}$
Total Depth.	

Drilled plug at 3446  
200' oil - 20 Min.  
Drilled deeper 3450'  
1000' oil 2 $\frac{1}{2}$  hrs.  
Drilled deeper 3453 $\frac{1}{2}$   
2800' oil 5 $\frac{1}{2}$  hrs.  
Drilled deeper 3455 $\frac{1}{2}$   
1500 gal acid.

Top Simpson 3422  
Top Arbuckle 3445 Ctd.