

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

Plotted
L.M.

DARBY PETROLEUM CORP.
Jorgenson No. 5


SEC. 7 T. 11 R. 17W.
NWc SW

Total Depth. 3354
Comm. 7-14-39 Comp. 7-28-39
Shot or treated. 500 gal.
Contractor.
Issued. 8-26-39

County Ellis.

CASING.

16" 108' 7" 3349'
10" 1112'



Elevation

Production. Pot. 3500B. Max.
Depthograph.

Figures Indicate Bottom of Formations.

shale and sand	108
shale red bed and iron	585
shale	655
sand	715
shale & red rock	1015
shaly shale & shells	1090
anhydrite	1093
anhydrite red bed and shale	1415
shale	1480
salt	1530
shale and shells	1695
lime and shale	2080
lime	2165
lime and shale	2450
shale	2480
shale and shells	2630
shale and lime	2780
shale	2838
shale and lime	3028
lime	3030
shale and lime	3350
lime	3354
Total Depth.	

Filled 1000' 30 Min. Drilled cement to 3350
Filled 1950' 1 hr 30 min. 2850' OIH in 5 hrs.
T.F.U. 3000'

Top Conglomerate	3325
Top Simpson Dolo.	3333
Top Arbuckle	3349