

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas


Company - HARRY GORE  
Farm - Stein

No. 1

SEC. 7 T. 11 R. 17W  
CE/2 NE SE

Total Depth. 3392 DFC  
Comm. 8-6-48 Comp. 8-21-48  
Shot or Treated.  
Contractor.  
Issued. 1-21-50

County. Ellis  
KANSAS



Elevation. 1853 ft.

Production. 26 bbls.

CASING:

8 5/8" 1095' cem w/500 sx. circ.  
5 1/2" 3390 1/2' cem w/100 sx.

Figures Indicate Bottom of Formations.

surface clay	40
shale, and	50
sand	65
shale, shells	380
sand, shale	430
sand	460
shale, shells	620
sand	765
shale	790
red bed	845
shale red	885
red bed	992
anhydrite	1140
shale red	1425
salt	1595
salt, shale	1660
shale, shells	1936
lime sdy	2024
lime	2104
lime, shale	2534
shale	2665
lime, shale	2854
lime	2975
lime, shale	3021
lime	3394

3394 = 3392 DFC

Total Depth

Tops:

Heebner shale	3032-34
Lansing K. C.	3075
Conglomerate	3338
Simpson shale	3357
Arbuckle	3390