

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg., Wichita, Kansas.

Plotted

P. E. J.

DICKEY OIL CO.
Stein No. 1.

SEC. 7 T. 11 R. 17W.
NW NW SE

Plotted Texas CO.

County Ellis.

Total Depth. 3450


Comm. 6-21-38 Comp. 8-6-38

Shot or Treated.

Contractor.

Issued. 9-10-38

SEP 10 1938



CASING.

15 $\frac{1}{2}$ " 69' 10" 1161'
7" 3447'

Elevation.

Production. Pot. 1011 B.

Figures Indicate Bottom of Formations.,

surface	69
shale and shells	670
sand	924
red bed shells & iron	1040 ✓
red bed	1149
anhydrite	1174
sd. limo	1198
red rock	1280
shale and shells	1320
red rock and shells	1360
shale	1395
shale and shells	1498
salt and shale	1690
shale and shells	1764
limo	1780
broken limo	1995
limo	2035
broken limo	2173
limo	2300
red bed	2310
broken limo	2389
limo	2425
shale	2445
broken limo	2456
limo and shale	2490
broken limo	2552
limo and shale	2896
limo	2940
shale and limo	2962
broken limo	2990
limo	3090
broken limo	3108
limo	3367
shale	3403
cherty conglomerate	3422
conglomerate	3425
simpson	3447
siliceous limo	3450

Total Depth.