


Plotted for

DICKEY OIL CO.
 Carmichael "D" No. 1.

SEC. 8 T. 11 R. 17 W
 CS $\frac{1}{2}$ SW SW

Total Depth. 3375'
 Comm. 9-15-41 Comp. 10-6-41
 Shot or Treated.
 Contractor.
 Issued. 12-27-41

County. Ellis



CASING:
 15 $\frac{1}{2}$ " 37'
 10 $\frac{3}{4}$ " 1095'
 7" 3366'

Elevation.

Production. Pot. 3000 B.

Figures Indicate Bottom of Formations.

sand & gravel	37
gravel	60
shale & shells	300
sand, wtr	340
shale	400
sand	465
shale	595
sand	735
red bed	1080
anhydrite	1120
shale & shells	1275
red bed	1303
shale	1435
salt	1625
shale & shells	1896
lime brkn	2190
shale	2295
shale & shells	2790
lime Topeka	2826
oil sat. 2973-2985	
lime	3092
lime & shale	3100
lime K.C.	3136
lime	3290
lime & shale	3315
red bed	3325
conglomerate	3349
dolomite	3358
shale green	3366
Arbuckle	3375
Total Depth.	

Tops: Topeka 2790
 K. C. 3100
 Arbuckle 3365 $\frac{1}{2}$ Corr. to DF