


WELL LOG BUREAU — KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - BRIDGEPORT OIL CO., INC.
Farm - Jorgensen "A" No. 1

SEC. 8 T. 11 R. 17 W
SWc SE

Total Depth. 3408'
Comm. 6-2-45 Comp. 6-25-45
Shot or Treated.
Contractor.
Issued. 7-14-45

County. Ellis
KANSAS



CASING:
8 5/8" 177' Cem.

Elevation. _____

Production. Dry

Figures Indicate Bottom of Formations.

sand	0-15
shale & sand	177
shale, clay & lime shells	330
sand	390
shale & shells	590
sand	735
sand & shells	800
shale & lime shells	1050
sand & pyrite iron	1100
anhydrite	1127
shale	1752
shale & lime shells	1860
shale & shells	1980
shale sdy	2040
shale	2080
lime	2160
lime & shale	2340
shale & lime shells	2380
lime & shale	2485
shale & lime shells	2548
shale	2710
lime & shale	2760
shale	2840
lime	2952
lime & shale	3053
lime	3093
shale	3146
lime	3341
chert	3345
chert & shale	3360
shale	3376
lime & shale	3408
Total Depth.	

Formation Tops: DF

Topeka	2830
Heebner	3104
Brown lime	3129
Lansing	3142
Conglomerate	3341
Simpson	3370
Arbuckle	3404