


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - WESTGATE-GREENLAND OIL CO.
Farm - Simpson No. 1

SEC. 9 T. 11 R. 17W
NW NW SE

Total Depth. 3497' PB 3272'
Comm. 1-28-48 Comp. 4-15-48
Shot or Treated. Acidized
Contractor. Jackson Drlg. Corp.
Issued. 9-11-48

County. Ellis KANSAS



Elevation. 1810 Ind.

CASING:

8 5/8" 838'9" Cem w/375 Sx.
5 1/2" 3459'7" Cem w/150Sx.

Production.
Temp. Pot. 25 Bbls. Oil

Figures Indicate Bottom of Formations.

surface sand	40
shale and sand	90
shale and shells	330
sand	360
shale and pyrite	458
shale and shells	545
sand	690
red bed	1055
anhydrite	1090
red bed and shale	1150
shale and sand	1340
shale and shells	1760
lime, brkn	1910
lime and shale	2430
lime	2445
lime and shale	2670
shale	2765
lime and shale	2860
li e	3295
lime and conglomerate	3330
lime and shale	3363
shale and sand	3380
shale and lime sand	3387
Arbuckle lime	3440
lime	3485
Arbuckle	3497
total depth(Rotary)	
PB 3272	

Tops:
Arbuckle 3386'

Lane wells from 3114-3124, 3214-3223.

3238-3398. P.B to 3272'

Acidized with 1000 GA Dowell Service	3238-3396
1000 GA "	3238-3396(additional)
4000 GA "	3214-3223
1000 GA "	3114-3124