


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
 508 East Murdock, Wichita, Kansas

Company- RAYMOND OIL CO.
 Farm- Simpson No. 2

SEC. 9 T. 11 R. 17W
 C N/2 SW SE

Total Depth. 3731'
 Comm. 10-21-60 Comp. 11-2-60
 Shot or Treated.
 Contractor.
 Issued. 1-23-61

County Ellis
 KANSAS



CASING:
 8 5/8" 1047' cem w/450 sx.
 5 1/2" 3500' cem w/150 sx.

Elevation. 1802' DF est.

Production. SWDW

	Figures Indicate Bottom of Formations.
shale & red bed	460
sand	690
shale	695
red rock	990
shale & red rock	1028
Anhydrite	1077
shale & shells	1740
shale & lime	2025
lime & shale	2185
sand	2205
lime & shale	2650
lime w/shale	2750
lime & shale	2987
shale	2991
lime & shale	3009
lime	3030
lime & shale	3080
lime	3152
lime & shale	3281
shale	3290
lime	3301
chert & shale	3379
dolomite & shale	3410
dolomite	3731 RTD
Total Depth	

TOPS:

Anhydrite (driller's)	1028
Heebner	2987
Toronto	3009
Lansing	3030
Base Kansas City	3281
Conglomerate	3301
Arbuckle	3379