

KANSAS

PI

WELL COMPLETION REPORT AND  
DRILLER'S LOGState Geological Survey  
WICHITA BRANCHAPI No. 15 — 051 — 22,433  
County Number

Operator

Liberty Enterprises, Inc.

Address

308 West Mill

Well No.

#1

Lease Name

Simpson "D"

Footage Location

330 feet from (N) ~~36~~ line 330 feet from (E) (W) line

Principal Contractor

Geologist

Pioneer Drilling Company, Inc. Greg Issinghoff &amp; Kevin Adams

Spud Date

May 29, 1981

Date Completed

June 7, 1981

Total Depth

3461'

P.B.T.D.

3412'

Directional Deviation


Oil and/or Gas Purchaser

Mobil Pipe Line

S. 9 T. 11 S. R. 17 ~~EX~~ W

Loc. NE NE NE

County Ellis

640 Acres  
N

Locate well correctly

Elev.: Gr. 1836

DF 1839 KB 1841

## CASING RECORD

Report of all strings set—surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 $\frac{3}{4}$ "	8 5/8"	24#	232'	common	125	2% gel, 3% cc
Production	7 7/8"	4 $\frac{1}{2}$ "	10.5#	3441'	ASC	150	
Braden Head Squeeze					50/50 poz	170	6% gel

## LINER RECORD

## PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			1 per 3' (17 shots)		3374-3327
TUBING RECORD					
Size	Setting depth	Packer set at			
2" EVE	3406				

## ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Acid 2000 gallons mud acid. Swab back and sand frac with 12000# sand and 400 barrel gelled water.	3374-3327

## INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
7-11-81		Pumping			
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
	36 BOPD	bbls.	7 BWPD	bbls.	CFPB
Disposition of gas (vented, used on lease or sold)			Producing interval(s)		
			Conglomerate Chert		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Liberty Enterprises, Inc.		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Well No. #1	Lease Name Simpson "D"	OIL
S 9 T 11 R 17 E W		


### WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,  
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Geological & Completion Report Enclosed				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	<div> <div></div> <div>Charles G. Comeau</div> <div>Signature</div> <div>Petroleum Geologist</div> <div>Title</div> <div>July 28, 1981</div> <div>Date</div> </div>
---------------	---

84348