


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- TENNESSEE GAS TRANSMISSION CO.
Farm- Emma A. Richmond No. 1

SEC. 10 T. 11 R. 17W
SW SW NE

Total Depth. 3442'
Comm. 7-2-57 Comp. 7-14-57
Shot or Treated.
Contractor. Shelley-Miller Drlg. Co.
Issued. 8-31-57

County Ellis
KANSAS



CASING:
8 5/8" 244' cem w/175 sx.

Elevation. 1827' RB

Production. Dry

Figures Indicate Bottom of Formations.

Meas. from top of Rotary Bushing

sand	18
lime & shale	130
shale & shells	245
shale	458
sand	705
red bed	1043
anhydrite	1080
shale & shells	1580
lime & shale	2865
lime	3442 RTD
Total Depth	

TOPS:	
Anhydrite	1043
Topeka	2773
Heebner	3006
Toronto	3026
Lansing	3046
Base Kansas City	3303
Conglomerate	3334
Simpson	3364
Arbuckle	3400

DST #1 3080-3135', open 45 min, weak blow 12 min.
Rec. 13' mud, 20 min. IBHP 345#.
20 min. FBHP 118#, FP 42-48.

DST #2 3132-70', open 1 hr, fair blow thruout,
Rec. 87' wtry mud. 20 min IBHP 1075#,
20 min., FBHP 915#, FP 35-73.

DST #3 3332-60', open 1 hr., fair blow thruout
Rec. 135' Sli OCMSW, 20 min. IBHP 1170#,
20 min., FBHP 990#, FP 90-100.