


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- **ANDERSON & STRAIN DRILLING CO.**
 Farm- Simpson No. 1

SEC. 10 T. 11 R. 17W
 NE NW SW

Total Depth. 3390 R.B.
 Comm. 9-14-52 Comp. 9-25-52
 Shot or Treated.
 Contractor. Strain Drlg.
 Issued. 11-22-52

County Ellis
 KANSAS



Elevation. 1805 R.B.

Production. Dry

CASING:

8 5/8" 1027 cem. w/500 sx.
 5 1/2" 3389' R.B. cem. w/100 sx.

Figures indicate Bottom of Formations.

All meas. R.B.

sand & soil	35
post rock & shale	70
shale blue & shells	370
shale & shells	460
sand & shale	510
shale	550
sand (D ST)	695
shale, shells, iron	790
shale & redbed	860
shale, shells, redbed	995
redbed, shale	1020
Anhyd.	1060
shale & redbed	1260
shale & shells	1490
shale & sand	1570
shale, shells	1605
lime, shale	1940
lime	1960
lime & shale	2930
lime	3321
Congl.	3365
shale	3389
Arb. Dolo.	3390 R.B.
Total Depth	

Tops:

Anhydrite	1020
Topoka	2755
Lansing	3032
Congl.	3315
Arbuckle	3388

D.S.T. by Johnston Testing Co.
 3112-3125 tool open 1 hr. Rec. 1800'
 gas, 60' oil cut mud, 210' free oil,
 BHP 20 min. 940#.
 3302-3321' tool open 30 min. weak blow
 4 min. Rec. 10' slightly oil cut mud.
 BHP 20 min. 640#.

No el. log run