

Plotted
 Albert Wheeler

GULF OIL CORP.
 Fred Cress No. 1.


SEC. 12 T. 11 R. 17W
 Sec SE
 480' fr EL 330' fr SL

Total Depth. 3295'
 Comm. 4-9-37 Comp. 5-18-37
 Shot or Treated.
 Contractor.
 Issued. 8-21-37

County. Ellis

CASING:
 16" 280'
 10 $\frac{3}{4}$ " 978'
 6" 3285'

AUG 21 1937



Elevation.

Production. Pot. 2168 B.

Figures Indicate Bottom of Formations. No wtr.

sand & gravel	25	lime & shale	2150
lime	65	lime lgt hrd	2430
shale blue	225	lime & shale brkn	2454
lime shells & shale	300	lime brkn	2500
shale	325	shale grey	2518
sand	330	lime shells	2533
sand red	360	lime brkn chert	2606
gravel lgt	375	lime brkn	2671
gravel	391	lime & chert	2682
sandstone & shale	420	lime brkn	2707
sand & gravel	455	lime brkn lgt med	2730
sand	485	lime lgt hrd	2930
iron	494	shale blue sft	2939
gravel	550	shale blue	2950
sand & iron shells red	600	shale brown	2955
gravel	623	shale green	2960
sand & gravel	643	lime Kansas City	2988
iron	655	lime & shale	3005
lime & iron shells	690	lime	3020
lime shells & gravel	700	shale & lime	3050
lime shells & shale	720	lime	3094
red bed	740	lime sdy	3110
shale & lime shells	834	shale brown	3113
iron & shale	850	lime	3125
iron	860	lime shells & shale	3139
shale & shells	890	lime & shale breaks	3160
shale & iron	900	lime	3186
iron	910	shale break	3190
shale, iron & lime		lime lgt	3214
shells	958	shale brown	3222
anhydrite	965	lime & shale breaks	3233
anhydrite lime	980	lime & shale breaks	
lime	1000	lime lgt & blue	3265
shale	1130	lime shells & shale	3278
shale & lime shells	1217	shale green	3280
shale sticky	1255	sand & shale green	3285
shale red	1275	lime brown & chert	3295
shale blue	1452	Total Depth.	
salt	1480		
shale & lime shells	1623		
lime	1640	Siliceous lime 3285-3295	
lime shells	1670		
lime	1680		
lime hrd	1700		
lime	1720		
lime & shale	1740		
shale & lime shells	1785		
lime	1800		
shale & lime shells	1825		
lime lgt	1870		
lime	2005		
lime & shells brown	2040		
lime & shale lgt grey	2072		
lime sft lgt grey	2110		
shale bluesft	2130		