

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

Plotted
fm.

LARIO OIL & GAS COMPANY.
Cress No. 2-C

SEC. 13 T. 11 R. 17W
NW SW SW

County Ellis.

Total Depth. 3377 $\frac{1}{2}$
Comm. 9-14-39 Comp. 10-1-39
Shot or Treated.
Contractor. Springrose Drilling Co.
Issued. 11-4-39

CASING.

8" 1060'
5" 3366'



Elevation.

Production. Pot. 9481 B.
Echo.

Figures Indicate Bottom of Formations.

sand and shale	165
shale and red bed	400
red bed	498
sand	587
shale and sand	740
shale and red bed	970
red bed	1048
anhydrite	1060
anhydrite and lime	1085
anhydrite	1090
red bed shale and shells	1255
shale	1440
shale and shells	1635
broken lime	1665
lime	1710
broken lime	1805
lime	1860
broken lime	2080
lime	2125
broken lime	2240
lime	2275
broken lime	2440
shale	2630
shale and slate	2640
broken lime	2680
shale and shells	2840
lime	2870
broken lime	2895
lime	3075
broken lime	3165
lime	3265
broken lime	3310
shale	3325
broken lime	3366
Arbuckle lime	3377 $\frac{1}{2}$
Total Depth.	