


Plotted
J.M.

LARIO OIL & GAS CO.
 Cress No. 4-C.

SEC. 13 T. 11 R. 17W
 CS $\frac{1}{2}$ S $\frac{1}{2}$ SW

Total Depth. 3383'
 Comm. 11-23-39 Comp. 12-14-39
 Shot or Treated.
 Contractor. Springrose Drlg Co.
 Issued. 1-6-40

County. Ellis



CASING:
 8" 1083'
 5" 3376'

Elevation.

Production. Pot. 9969 B.

Figures Indicate Bottom of Formations.

surface clay & sand	80
shale	150
shale & shells	595
lime brkn	655
sand	725
shale & shells	820
lime brkn	945
shale red	1060
shale blue	1070
anhydrite	1119
red bed & shale	1240
shale & shells	1430
shale & salt	1640
shale & shells	1720
lime & shells	1750
lime brkn	1900
shale & lime	1945
lime brkn	2070
lime & sticky shale	2110
lime	2145
shale	2250
lime brkn	2270
shale & lime	2335
shale	2405
shale & lime	2500
shale & shells	2550
shale sdy	2575
shale	2675
shale & shells	2730
shale	2830
lime	2935
lime & chert	2970
lime	3040
shale & lime	3095
lime brkn	3140
lime	3355
lime, conglomerate & green shale	3382
chert & dolomite	3385
Steel Line Meas. Corr. to	3376
lime	3383
Total Depth.	

Top Lansing 3083
 Top Conglomerate 3343
 Top Simpson 3358
 Top Arbuckia 3376 Corr.