

PLOTTED
G.E. Jamison

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.


SINCLAIR PRAIRIE OIL CO.
Hugh I. Cress No. 3

SEC. 13 T. 11 R. 17W
NW SE NE
330' fr Nth & 990' fr E.L.
S $\frac{1}{2}$ NE $\frac{1}{4}$

Total Depth. 3348
Comm. 10-19-37 Comp. 11-11-37
Shot or Treated. 2000 gal.
Contractor. Hissom & Wolfe Drlg. Co.
Issued. 1-15-38

JAN 15 1938
County Ellis.

CASING. Rotary 3338
Cable 3348
16 $\frac{1}{2}$ " 99'
95/8" 1013'
7" 3334'
23' liner set at 3342.
3325 of 2 $\frac{1}{2}$ " tubing.



Elevation.

Production. Pot. 411 B.
no wtr

Figures Indicate Bottom of Formations.

shale and gravel	107
shale and shells	712
shale and red bed	827
shale and shells	1011
anhydrite	1056
shale and lime shells	1219
shale	1416
shale and shells	1646
shale	1695
lime broken	1798
shale lime shells	1882
lime	2138
lime broken	2223
lime	2421
shale and lime	2676
lime	3236
lime and conglomerate	3290
conglomerate	3310
sand and conglomerate	3328
shale	3334
lime Siliceous	3348
Total Depth.	

Top Siliceous 3334 $\frac{1}{2}$

At 3342 fill up 700' oil in 2 hours.
At 3348 fill up 3000' oil