

12  
G. E. James


GULF OIL CORP.  
Pearl No. 2.

SEC. 13 T. 11 R. 17W.  
SE NE SE

Total Depth. 3392.  
Comm. 1-21-38 Comp. 2-21-38  
Shot or Treated. 2000 Gal.  
Contractor.  
Issued. 4-2-38

APR 2 1938

County. Ellis.



CASING.

16" 159'  
10 3/4" 1094'  
6" 3388'

Elevation.

Production. Pot. 1936 B.

Figures Indicate Bottom of Formations.

cellar	8'6"
surface soil	60
shale	95
sand and shale	170
shale and shells	220
shale lime shells	395
shale and shells	455
sand & shale brkn	478
shale	495
sand	560
shale	675
sand	735
shale and shells	842
shale and red bed	986
shale and shells	1079
anhydrite	1119
red rock shale and shells	1280
shale and shells	1445
salt	1602
shale and salt	1638
shale	1650
broken lime	1713
shale and lime	1807
shale and shells	1901
lime shale broken	1991
lime	2153
shale	2160
shale broken lime	2255
lime and shale	2309
shale and shells	2370
broken lime shale	2410
shale lime shells	2490
broken lime	2537
shale and lime	2599
shale and broken lime	2672
lime and shale	2739
shale and shells	2780
broken lime	2810
lime	2886
broken lime	2929
lime	2957
lime very hard	2980
lime	3130
lime and shale broken	3175
lime	3313
shale and lime	3360
shale	3390
porous sdy lime	3392

Total Depth.

Siliceous lime 3387-3392