

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk Bldg., Wichita, Kansas

*Plotted  
L.M.*

LARIO OIL & GAS CO.  
Pearl No. 3.

SEC.13 T.11 R.17W  
CW $\frac{1}{2}$  SW SE

Total Depth. 3394'  
Comm. 4-20-40 Comp. 5-8-40  
Shot or Treated.  
Contractor. Springrose Drlg.Co.  
Issued. 6-8-40

County. Ellis



CASING:  
12 $\frac{1}{8}$ " 62'  
8 5/8" 1084'  
5 $\frac{1}{2}$ " 3391'

Elevation.

Production. Pot.3647 B.

Figures Indicate Bottom of Formations.

surface soil	62
clay & sand	200
shale blue	340
red beds	450
shale & red beds	650
sand	735
shale, sand, red beds	810
shale & red beds	1065
anhydrite	1120
shale & red beds	1230
sand	1400
shale	1435
shale & salt	1525
shale, shells, red beds	1860
shale sdy	1895
lime brkn	1990
shale & lime	2600
shale sticky	2645
shale & lime	2905
lime brkn	3100
lime	3150
lime brkn	3374
Simpson shale	3389
Simpson sand	3390
dolomite	3394
Total Depth.	