

Plotted
LN.

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

LARIO OIL AND GAS CO.
Pearl No. 4


SEC. 13 T. 11 R. 17W.
CE $\frac{1}{2}$ SW SE

Total Depth. 3378
Comm. 5-13-40 Comp. 6-4-40
Shot or Treated. 1500 gallons.
Contractor. Springrose Drilling Co.
Issued. 8-10-40

County Ellis

CASING.

12 $\frac{1}{2}$ "	54'
8"	1082'
5"	3374'



Elevation.

Production. Pot. 4995 B.

Figures Indicate Bottom of Formations.

clay shale and shells	215
shale and shells	480
sand and shells	670
sand	740
shale and red bed	780
shale lime shells	850
shale red bed	895
red bed and shells	1055
anhydrite	1130
red bed and shale	1425
salt	1500
shale and red bed	1645
shale and shells	1700
shale shells red bed	1825
shale and shells	1975
shale and lime	2485
shale and lime shells	2595
shale and lime	2750
broken lime	2935
lime	2990
broken lime	3371
Simpson sand	3373
Arbuckle	3378

Total Depth.