

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg. Wichita, Kansas

Company - WESTGATE_GREENLAND OIL COMP NY
Farm - Hall No. 1

SEC. 14 T. 11 R.17W
SE SW NE

DEEPENING RECORD:

Total Depth. 3930
Comm. 12-10-47 Comp. 12-23-47
Shot or treated.
Contractor. Jackson Drilling Corp.
Issued. 5-20-50

County. Ellis
KANSAS



CASING:

8-5/8" 767' Cem. w/400 sx

Elevation. 1833 Ind

Production. Dry

Figures indicate Bottom of Formations.

surface clay & sand	0-35
shale & shells	125
shale	275
shells & sand	325
shale & shells	345
sand	362
shale & shells	600
sand	700
shale & shells	710
shale red	870
shale & shells	962
shale sdy & shells	1062
anhydrite	1100
red rock & shale	1166
shale & shells	1532
shale	1850
lime & shale	1980
shale & lime shells	2062
lime & shale	2131
lime	2350
shale & lime	2364
lime	2445
lime & shale	2824
lime	2895
lime & shale	3009
lime	3075
lime & shale	3150
lime	3345
conglomerate	3379
lime	3493
Total Depth	

DEEPENING RECORD:

Company: CITIES SERVICE OIL CO.
Comm: 10-15-49
Comp: 10-18-49
Contractor: Herndon Drlg. Co.
Acid. 3000 gals.
Production: Input well
5 1/2" 3446' cem w/250 sx.
Old total depth 3493'

lime	3635
lime, shale	3665
lime	3830
lime, shale, sand	3920
granite wash	3930
Total depth	

Tops:
Conglomerate 3320
Arbuckle 3403
Quartz-Mica Schist 3924
Penetration 6'

Pumped 200 sx. cement thru Bradenhead
between 8 5/8" and 5 1/2" casing to
shut off Dakota water.

Tops:
Conglomerate 3320
Arbuckle 3403