


CITIES SERVICE OIL CO.
Hall No. 2-A.

SEC. 14 T. 11 R. 17W.
SE SW SW
330' N. 978.55E of SW Cor.

Total Depth. 3388
Comm. 12-24-37 Comp. 1-21-38
Shot or Treated.
Contractor. Corbett and Barbour
Issued. 2-26-38

County Ellis.

FEB 26 1938



CASING.

15 $\frac{1}{2}$ " 131'
10 $\frac{3}{4}$ " 1102'
7" 3388'

Elevation.

Production. Pot. 2664 B.
no wtr. 24 hr.
Nat.

Figures Indicate Bottom of Formations.

surface	96	
shale and shells	425	
red bed	547	
sand shale shells	675	
red bed	1103	
anhydrite	1175	
red bed	1391	
shale and shells	1475	
salt	1610	
shale and shells	1730	
broken lime & shale	1820	
shale and shells	1900	
broken lime	1965	
lime	2013	
lime and shale	2080	
lime	2161	
broken lime	2440	
shale lime shells	2548	
shale and shells	2660	
slate & lime shells	2707	
shale & lime shells	2779	
Topeka lime	2883	
lime	3170	
lime K.C.	3210	
lime	3287	
K.C. lime(S.O.light)	3322	
(3302-06)		
shale	3326	
shale and shells	3373	
lime	3379	
shale & sdy shale	3382	cored
conglomerate	3383	cored
lime	3384	cored
SLM corr. 3384 equals	3381	
lime	3388	

Total Depth.

Top of Arbuckle 3380 SLM
Pen 8'

Pay 3381-83 and 3385-87