


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg., Wichita, Kansas.

GULF OIL CORPORATION.
Henry Mai No. 4

SEC. 14 T. 11 R. 17W.
SW SE SE

Total Depth. 3392.
Comm. 6-6-39 Comp. 6-24-39
Shot or Treated.
Contractor.
Issued. 8-5-39

County Ellis.



CASING.

16" 51'
95/8" 1110'
7" 3391'

Elevation.

Production. Pot. 3500 B.

Figures Indicate Bottom of Formations.

shale blue	54
shale and shells	300
sand and shells	385
shale and shells	785
shale and sand	850
red bed	900
shale and sand	990
shale	1086
chalk	1090
anhydrite	1118
shale and lime shells	1315
shale and shells	1465
salt and shale	1580
salt and shells	1640
shale and lime	1730
lime	1760
shale	1950
lime	2010
lime and shale	2135
lime	2160
lime and shale	2325
lime	2460
shale and lime	2515
lime	2550
shale	2668
lime	3090
lime and shale	3130
lime	3374
shale	3380
lime	3392
Total Depth.	

Arbuckle Lime 3390-3392