

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk Bldg., Wichita, Kansas


*Plotted*  
*J.M.*

GULF OIL CORP.  
Henry Mai No. 6.

SEC. 14 T. 11 R. 17W  
NE SE SE

Total Depth. 3372'  
Comm. 7-10-39 Comp. 8-1-39  
Shot or Treated.  
Contractor.  
Issued. 9-18-39

County. Ellis



CASING:  
16" 73'  
9 5/8" 1070'  
5 1/2" 3371'

Elevation.

Production. Pot. 3500 B.Max.  
Depthograph  
No water

Figures Indicate Bottom of Formations.

clay yellow	30
shale sdy	40
sand & gravel	50
sand	60
shale blue	75
shale & sand	300
red bed	430
sand, shale, red bed	735
shale, shells, red bed	930
red bed & shale	1063
anhydrite	1095
shale	1150
red bed	1305
gy shale & shells	1375
shale	1395
salt & shale	1550
shale & shells	1640
shale	1810
lime brkn	1905
lime	2000
shale	2020
shale & lime	2110
lime	2210
shale & lime	2280
lime	2305
shale & lime	2345
lime	2365
shale	2465
lime	2500
shale	2555
shale & lime	2675
shale & lime shells	2775
shale	2780
lime	3060
shale	3082
lime	3372
Total Depth.	

Potential test taken with  
Depthograph, well allowed  
maximum potential of 3500 B.