


Plotted
J.P.M.

GULF OIL CORP.
Henry Mai No. 7

SEC. 14 T. 11 R. 17W.
SE NE SE

Total Depth, 3361
Comm. 10-21-39 Comp. 11-16-39
Shot or Treated.
Contractor.
Issued, 12-30-39

County Ellis.



CASING.

13" 129'
5 1/2" 3359'

Elevation.

Production, Pot. 3500 B.
No wtr, Deptho.

Figures Indicate Bottom of Formations.

surface clay and sand	40
sand and surface shale	100
shale dark	135
shale light blue	335
sand and chat	355
red bed	385
shale blue and sand	435
shale blue	474
sand	548
pyrite (iron)	553 ✓
shale blue	600
shale and sdy lime	810
shale and lime sholls	1060
anhydrite	1085
shale and sholls blue and red	1140
red and grey shale and sholls	1275
shale grey and lime sholls	1375
shale and lime sholls	1425
salt and shale broaks	1560
shale blue and salt	1590
anhydrite and dark grey lime	1615
shale blue and sholls	1660
anhydrite	1715
limo dark and anhydrite sholls	1725
shale and limo sholls	1870
shale blue and sholls	1940
shale grey and limo sholls hard	2055
limo	2155
limo and shale	2190
chert	2196
shale rod	2230
limo grey with small blue shale broaks	2277
limo	2300
limo and shale	2320
limo sholls and shale	2350
limo	2370
shale and sholls	2376
shale blue and limo	2412
shale grey and limo	2455
shale and limo	2478
shale blue and grey and limo sholls	2552
sdv blue shale and sholls	2590
limo	2604
shale blue and limo	2632
shale blue and limo	2685
shale grey with hard limo stroaks	2740
limo and shale broaks	2788
limo and shale broaks	2830
shale blk and sholls	2899
limo	2919
shale blue and sholls	2959
limo hard with shale strks	2998
limo	3346
limo and shale	3358
limo	3361

Arbucklo limo 3359-3361

Total Depth.