

State Geological Survey
WICHITA, BRANCH

14-11-17W
RECEIVED
STATE CORPORATION COMMISSION

JUL 25 1980

CONSERVATION DIVISION
Wichita, Kansas

WELL LOG

OPERATOR: Robert R. Price

WELL NAME: Mai #11

LOCATION: C N/2 S/2 SE/4 14-11S-17W

COUNTY: Ellis

STATE: Kansas

WELL COMMENCED: June 27, 1980

WELL COMPLETED: July 4, 1980

ELEVATION: 1852' K.B.

TOTAL DEPTH: 3359'

PRODUCTION: Oil

RIG NO: #1

CASING - 8-5/8": 239.79' of used 28# cemented with 110 sxs common 3% cc 2% gel cement circ

5-1/2": 3358' of used 13.5# cemented with 150 sxs of Dowell RFC plugdown @ 12:30 A.M.

ALL MEASUREMENTS TAKEN FROM THE TOP OF ROTARY BUSHING:

FROM	TO	FORMATION	DEVIATION. FROM VERTICAL	REMARKS:
0'	248'			
248'	327'	shale		
327'	1059'	shale and sand		
1060'	1083'	Anhydrite		
1083'	1095'	Anhydrite		
1095'	1702'	shales		
1702'	1788'			
1788'	2092'	shale and lime		
2092'	2390'	shales and limes		
2390'	2638'	lime and shales		
2638'	2700'	shale and lime		
2700'	2796'	shales and limes	2700' - 3/4 degrees	
2796'	2880'	lime		
2880'	2928'	lime and shale		
2928'	2928'			
2928'	3010'			
3010'	3127'	lime and shale		
3127'	3236'	lime and shale		
3236'	3326'	Kansas City		
3326'	3340'	lime and shale		
3340'	3359'	lime and shale		
3359'	RTD			