


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
 508 East Murdock, Wichita, Kansas

Company- **MURFIN DRILLING CO.**
 Farm- **Simpson** No. 2

SEC. 14 T. 11 R.17W
 NW NE NW

Total Depth. **3371'**
 Comm. **8-18-58** Comp. **8-26-58**
 Shot or Treated.
 Contractor. **Murfin Drlg.**
 Issued. **1-10-59**

County **Ellis**
KANSAS



CASING:
 8 5/8" 202' cem w/150 sx.

Elevation. 1821' KB

Production. **Dry**

Figures indicate Bottom of Formations.

surface hole	202
shale-shells	450
sand-shale	540
hard sand-pyrite	560
sand	690
red bed	700
red bed - shells	965
red bed	1033
Anhydrite	1070
shale - shells	1400
salt - shale	1595
shale - lime shells	1765
shale	1935
lime - shale	3065
lime	3275
lime - Conglomerate	3335
Conglomerate	3340
Simpson	3366
Arbuckle (Dolomite)	3371
Total Depth	

TOPS:

Anhydrite	1033
Heebner Shale	2979
Toronto Lime	2999
Lansing-Kansas City	3020
Conglomerate	3285
Simpson Dolomite	3340
Simpson Shale	3347
Simpson Sand	3364
Arbuckle Dolomite	3366

DST #1 3117-3127, op 1 hr., rec. 30'
 WO specked M. BHP 9# in 30 min.

DST #2 3227-3260, op 1 hr., rec. 30' OCM.
 BHP 800# in 30 min.

DST #3 3345-3371, op 1 hr., rec. 570' SW
 trace O & G. IFP 140#, FFP 380#, BHP
 1100# in 30 min.