


*Plot
2 Nov 1937*

THE TEXAS CO.
F. A. Bemis No. 1-B.

SEC. 15 T. 11 R. 17W
SW¹/₄ NW
Approx. 330' fr S & WL NW¹/₄

Total Depth. 3424'
Comm. 2-18-37 Comp. 4-6-37
Shot or Treated.
Contractor. Mac & Stauffer Drlg. Co.
Issued. 5-22-37 Rotary O-3421
Casing: Cable 3421-24
15¹/₂" 120'
10 " 1112'
7 " 3421'

County. Ellis



Elevation.

Production. Pot. Pump
475 B, 12% W.

Figures Indicate Bottom of Formations.

soil, sand & shale	123
lime	338
shale & lime shells	440
lime	500
shale	600
lime	635
sand	745
shale & lime shells	805
shale	835
lime	860
lime hrd	885
brkn lime	903
shale & lime shells	1075
lime	1080
brkn lime	1090
chalk	1097
anhydrite	1107
anhydrite	1120
red bed & lime shells	1125
red bed	1204
lime	1350
shale	1579
shale brown	1620
shale & lime shells	1640
shale	1670
brkn lime	1747
lime	1825
shale	1910
lime hrd	1962
lime	2428
sticky shale	2516
shale	2668
brkn lime	2702
shale	2843
lime	3373
Lost circulation at 2898	
conglomerate	3407 ¹ / ₂
lime	3414
lime cored	3424
Total Depth.	