

Operator Richard H. Zinszer DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

Well No. 9 Lease Name Bemis 'B' Oil Well

S 15 T 11 S R 12 W 120" NW-NW-NE-SW

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Anhydrite	1058'			
Base Anhydrite	1094'			
Topeka Lime	2787'			
Queen Hill Shale	2948'			
Heebner Shale	3018'			
Toronto Lime	3039'			
Lansing-K.C.	3062'			
Base-K. C.	3304'			
Conglomerate Chert	3322'			
Simpson Dolomite	3358'			
Arbuckle Dolomite	3384'			
DST #1 Recovery: 20' Mud 30" - 45" - 45" - 60" IFP: 9-13# ISIP: 598# FFP: 19-28# FSIP: 598# BHT: 92° F	3140'	3165'		
DST #2 Recovery: 50' Mud 30" - 45" - 45" - 60" IFP: 9-9# ISIP: 286# FFP: 19-28# FSIP: 249# BHT: 93° F	3327'	3384'		

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received _____

Richard H. Zinszer
Signature

Part owner
Title

1/31/80
Date

45278