

THE BLACKWELL OIL & GAS CO.
Richmond No. 2.

SEC. 15 T. 11 R. 17W
SE SE SE
330' N SL 2310' E WL

DEC 25 1937


Total Depth. 3410'
Comm. 10-29-37 Comp. 12-5-37
Shot or Treated.
Contractor.
Issued. 12-25-37

County. Ellis

CASING:

15 1/2" 18'
10 " 1015'
7 " 3396'6"

Rotary O-3399
Cable 3399-3410



Elevation.

Production. Pot. 2000 B.

Figures Indicate Bottom of Formations.

surface	18	Siliceous lime 3398-3410
shale & shells	370	
clay, sand particles	841	
red bed & shale	1060	
shale	1100	
lime & shale	1200	
red bed & shells	1387	
shale	1418	
salt & shale	1515	
sdv shale	1600	
lime & shale	1716	
lime	1812	
lime & shale brks	1860	
shale & lime shells	1896	
shale	1975	
lime	2052	
brkn lime & shale	2088	
lime	2100	
shale	2110	
shale & lime	2190	
lime & shale brks	2333	
lime & shale	2510	
shale	2591	
sdv shale	2700	
shale & lime	2865	
lime	3087	
lime & shale	3092	
shale & red rock	3108	
lime	3325	
brkn lime & shale	3335	
red rock	3341	
brkn lime & chert	3367	
conglomerate	3375	
Simpson dolomite, strks of		
green shale	3385	
sdv shale sprinkled with		
bright green	3398	
lime	3399	
lime Siliceous	3406	
Started swabbing oil		
lime drilled	3410	
Total Depth.		

Made approx. 2000 bbls n Pot. tests