


WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - TEXAS CO.
Farm - V. Richmond No. 1.

SEC. 15 T. 11 R. 17 W
C E₂ SW NE

Total Depth. 3540'
Comm. 10-15-44 Comp. 11-2-44
Shot or Treated.
Contractor. Helmerich & Payne, Inc.
Issued. 12-30-44 Rotary 0-3540

County. Ellis
KANSAS



CASING:
9 5/8" 1140' Cem.

Elevation. _____

Production. Dry

Figures Indicate Bottom of Formations.

sand	120	Tops:	
shale	230	Lansing	3170
sand	300	Base K. C.	3380
shale	370	Congl.	3406
sand	425	Simpson	3475
shale & shells	675	Arbuckle	3490
sand	800		
shale & shells	890	No show	
red bed	960		
sand	1002		
shale	1062		
shale & shells	1110		
shale & shells	1140		
anhydrite	1151		
lime	1170		
shale & shells	1182		
shale	1242		
red bed	1370		
shale	1485		
shale & shells	1700		
salt & shale	1790		
shale & lime	2140		
shale & shells	2240		
lime & shale	2260		
sand	2268		
lime & shale	2302		
sand	2316		
lime & shale	2335		
lime	2400		
shale & shells	2510		
lime brkn & shale	2550		
lime & shale	2590		
lime brkn	2665		
shale & shells	2738		
lime brkn & shale	2830		
shale & lime	2862		
shale & shells	2874		
lime & shale	2876		
Topeka lime	2905		
porous lime	2930		
lime brkn	2998		
lime	3108		
lime & shale	3230		
lime	3252		
lime & shale	3338		
cong.	3360		
lime & shale	3412		
lime sft	3442		
lime & shale	3490		
cong	3508		
lime & chert	3540		
Total Depth			